



Filing Receipt

Filed Date - 2026-03-16 12:51:28 AM

Control Number - 53385

Item Number - 4955



Public Utility Commission of Texas
Executive Summary Template for 16 TAC § 25.53 EOP Filings

Executive Summary

16 Texas Administrative Code (TAC) § 25.53 requires all Texas electric entities to file an Emergency Operations Plan (EOP) annually. This rule establishes requirements for the annual EOP filing. As part of the annual EOP filing, entities must file an executive summary that provides entity information, summarizes EOP content, and includes a signed affidavit affirming personnel training, business continuity, and other requirements as detailed in 16 TAC § 25.53.

In accordance with 16 TAC § 25.53, **SMT Ironman BESS, LLC** (Alvin) hereby files its updated Emergency Operations Plan ("EOP").



Public Utility Commission of Texas
Executive Summary Template for 16 TAC § 25.53 EOP Filings

Entity Information

Entity Legal Name: SMT Ironman BESS, LLC

Entity ID Number¹: 20820

Entity Type: Power Generation Company (PGC)

Entity Power Region²: ERCOT

Joint Filing

If the filing is a joint filing for multiple entities registered with the Public Utility Commission of Texas, provide a list of all jointly filing entities in **Attachment 1**. If this does not apply, write **N/A** in the attachment.

Generation Facilities

If the filing includes multiple generation facilities within a single registration, provide a list of all applicable generation facilities that are included in the EOP filing in **Attachment 2**. If this does not apply, write **N/A** in the attachment.

Generation Facility Changes

Note any changes in Generation facilities that occurred since the previous filing (ex: changes in generation output, purchasing or selling of assets), complete **Attachment 3** with a description of changes. If no changes were made, write **N/A** in the attachment.

¹ The entity registration number issued by PUCT or ID number assigned by PUCT.

² Select the entity's power region using the drop-down list. The options are ERCOT, MISO, and SPP.



EOP Filing Requirement Mapping

The table below includes the 16 TAC § 25.53 requirements required by all reporting entities.

Instructions: Complete the below EOP roadmap to fulfill the requirements to include a reference to specific sections and page numbers of the entity's EOP that correspond with the requirements of this rule.

16 TAC § 25.53	Description	Applicable Document(s)	Page(s)
(c) (1) (A) (i)	Executive Summary		3
(c) (3)	Continuous Maintenance of EOP		8
(c) (4) (A)	Record of Distribution		5
(c) (4) (B)	Emergency Contacts		3
(c) (4) (C)	<i>Signed Affidavit from Entity's Highest-Ranking Representative Affirming the Following:</i>		6
(c) (4) (C) (i)	Relevant Personnel are Familiar With and have Received Training on the EOP		6
(c) (4) (C) (ii)	Reviewed and Approved by Appropriate Executives		6
(c) (4) (C) (iii)	Drills Have Been Conducted to the Extent Required		6
(c) (4) (C) (iv)	Distributed to Local Jurisdictions		6
(c) (4) (C) (v)	Business Continuity Plan		6
(c) (4) (C) (vi)	Personnel Training (IS-100, IS-200, IS-700, IS-800 NIMS)		6
(d) (1) (A)	Approval and Implementation Section Introduction		8
(d) (1) (A)	Outline of Applicability		3
(d) (1) (B)	List of Individuals Responsible for Maintaining and Implementing EOP		8
(d) (1) (B)	List of Individuals who Can Change EOP		8
(d) (1) (C)	Revision Control Summary		10
(d) (1) (D)	Dated Statement of Approval Adopting the Plan and Superseding Previous Plan		10



Public Utility Commission of Texas
Executive Summary Template for 16 TAC § 25.53 EOP Filings

16 TAC § 25.53	Description	Applicable Document(s)	Page(s)
(d) (1) (E)	Most Recent Approval Date		10
(d) (2)	Communication Plan		10
(d) (3)	Plan to Maintain Pre-identified Supplies for Emergency Response		12
(d) (4)	Staffing During Emergency Response		12
(d) (5)	Identification of Weather-related Hazards and Activation of EOP		14
(f)	Annual Drill Information		13



EOP Filing Requirement Mapping – Transmission and Distribution

The table below includes the 16 TAC § 25.53 annex requirements specific to electric utilities, transmission and distribution utilities, municipally owned utilities, and electric cooperatives.

Instructions: Complete the below EOP roadmap to fulfill the requirements to include a reference to specific sections and page numbers of the entity's EOP that correspond with the requirements of this rule.

16 TAC § 25.53	Description	Applicable Document(s)	Page(s)
(e) (1) (A) (i)	Weather Emergency Annex Operational Plans		
	Cold Weather		
	Hot Weather		
(e) (1) (A) (i)	Weather Emergency Annex Checklists		
	Cold Weather		
	Hot Weather		
(e) (1) (B)	Load Shed Annex		
(e) (1) (C)	Pandemic and Epidemic Annex		
(e) (1) (D)	Wildfire Annex		
(e) (1) (E)	Hurricane Annex		
(e) (1) (F)	Cyber Security Annex		
(e) (1) (G)	Physical Security Annex		
(e) (1) (H)	Flood Annex		
(e) (1) (I)	Additional annexes as needed or appropriate to the entity's particular circumstances		
(e) (2)	Annex for the use of PURA Facilities		



EOP Filing Requirement Mapping – Generation

The table below includes the 16 TAC § 25.53 annex requirements specific to a PGC or an electric cooperatives, electric utilities, and municipally owned utilities that operate a generation resource in Texas.

Instructions: Complete the below EOP roadmap to fulfill the requirements to include a reference to specific sections and page numbers of the entity's EOP that correspond with the requirements of this rule.

16 TAC § 25.53	Description	Applicable Document(s)	Page(s)
(e) (3) (A) (i)	Weather Emergency Annex - Operational Plans		
	<i>Cold Weather</i>		19
	<i>Hot Weather</i>		20
(e) (3) (A) (ii)	Weather Emergency Annex - Verification of Adequacy and Operability of Fuel Switching Equipment	N/A	
(e) (3) (A) (iii)	Weather Emergency Annex – Checklist for Generation Resource Personnel to Use		
	<i>Cold Weather</i>		20
	<i>Hot Weather</i>		21
(e) (3) (B)	Water Shortage Annex	N/A - The facility does not require process water to operate.	
(e) (3) (C)	Restoration of Service Annex		22
(e) (3) (D)	Pandemic and Epidemic Annex		22
(e) (3) (E)	Hurricane Annex		22
(e) (3) (F)	Cyber Security Annex		23
(e) (3) (G)	Physical Security Annex		24
(e) (3) (H)	Flood Annex		24
(e) (3) (I)	Additional annexes as needed or appropriate to the entity's particular circumstances		



EOP Filing Requirement Mapping – Retail Electric Provider

The table below includes the 16 TAC § 25.53 annex requirements specific to Retail Electric Providers.

Instructions: Complete the below EOP roadmap to fulfill the requirements to include a reference to specific sections and page numbers of the entity's EOP that correspond with the requirements of this rule.

16 TAC § 25.53	Description	Applicable Document(s)	Page(s)
(e) (4) (A)	Pandemic and Epidemic Annex		
(e) (4) (B)	Hurricane Annex (gen, T&D, REP)		
(e) (4) (C)	Cyber Security Annex		
(e) (4) (D)	Physical Security Annex		
(e) (4) (E)	Additional annexes as needed or appropriate to the entity's particular circumstances		



Public Utility Commission of Texas
Executive Summary Template for 16 TAC § 25.53 EOP Filings

Record of Distribution

Instructions: Complete **Attachment 4** to fulfill the requirement to complete a record of distribution of the EOP to all applicable **SMT Ironman BESS, LLC** personnel.

Affidavit

Instructions: Include a signed affidavit from the entity's highest-ranking representative that confirms the requirements in 16 TAC §25.53(c)(4)(C) have been met. 16 TAC §25.53(c)(4)(C) is referenced in the Executive Summary requirements description above.



Attachment 1. Joint Filing Entity Names

If the filing is a joint filing for multiple entities registered with the Public Utility Commission of Texas, provide a list of all registered entities included in the EOP filing in the table below.

Note: If the joint filing contains more than ten (10) entities, add more rows to the table as needed to accommodate the number of entities in the filing. There should be one (1) row for each legal entity.

Legal Entity Name	Entity ID Number(s)	Entity Type	Entity Power Region(s)

N/A



Attachment 2. Power Generation Facilities

If the filing includes multiple generation facilities within a single registration, provide a list of all applicable generation facilities that are included in the EOP filing in the table below.

Note: If the joint filing contains more than fifteen (15) facilities, add more rows to the table as needed to accommodate the number of generation facilities in this filing. There should be one (1) row per generation facility.

Generation Facility Name	Generation Facility Location

N/A



Attachment 3. Generation Facility Changes

Provide a list of all changes in Generation facilities from previous filing. This includes the purchasing or selling of assets, changes in generation output, or change of a facility to mothball or decommissioned status. There should be one (1) change per row. If there are no changes, enter N/A in the first line. Add more lines to the table, as needed.

Generation Facility Name	Generation Facility Change

N/A



Attachment 4. Record of Distribution

Instructions: Complete the table below to fulfill the requirement to complete a record of distribution of the EOP to all applicable **SMT Ironman BESS, LLC** personnel.

Note: Please add additional rows to the record of distribution table, as needed. There should be one (1) row per distribution.

Record of Distribution		
Distributed To	Date Distributed	Approved By
America Alatorre	February 2025	Kellie Macpherson
Jay Peterson	February 2025	Kellie Macpherson
Kevin Feely	February 2025	Kellie Macpherson
Dan Barnard	February 2025	Kellie Macpherson
Jonathan Garcia	February 2025	Kellie Macpherson
Paul Morris	February 2025	Kellie Macpherson
Daniel Lynch	February 2025	Kellie Macpherson
Levi Parker	February 2025	Kellie Macpherson

SMT Ironman BESS, LLC	
POLICY NAME	Emergency Operations Plan
EFFECTIVE DATE	2/20/2026
VERSION NO.	3.0

SMT IRONMAN BESS, LLC EMERGENCY OPERATIONS PLAN | TABLE OF CONTENTS

1.0	EXECUTIVE SUMMARY.....	3
2.0	ROLES AND RESPONSIBILITIES.....	7
3.0	APPROVAL, IMPLEMENTATION, AND REVISION CONTROL.....	8
4.0	COMMUNICATION PLAN.....	10
5.0	PLAN TO MAINTAIN PRE-IDENTIFIED SUPPLIES.....	12
6.0	EMERGENCY STAFFING PLAN.....	12
7.0	TRAINING.....	13
8.0	LOCAL EMERGENCY CONTACTS.....	13
9.0	WEATHER HAZARD IDENTIFICATION AND EOP ACTIVATION PROCEDURE.....	14
10.0	PERSONNEL INJURIES OR SERIOUS HEALTH CONDITIONS.....	14
11.0	FIRE RESPONSE PLAN.....	16
12.0	CHEMICAL OR OIL SPILLS AND RELEASES.....	17
	WEATHER EMERGENCY ANNEX.....	19
	WATER SHORTAGE ANNEX.....	22
	RESTORATION OF SERVICE ANNEX.....	22
	PANDEMIC AND EPIDEMIC ANNEX.....	22
	HURRICANE ANNEX.....	22
	CYBERSECURITY ANNEX.....	27
	FLOODING ANNEX.....	28

1.0 EXECUTIVE SUMMARY

1.1 Facility Information

SMT Ironman BESS, LLC (Ironman) Facility is a 304.25 MWac BESS facility located in Brazoria County, Texas. The Facility commenced commercial operations in Q2 of 2025 and is interconnected to ERCOT at the 345 KV Oasis substation located in the TRE footprint. The Facility is located in Region 4 of the Texas Division of Emergency Management.

1.2 Public Utility Commission of Texas

In accordance with 16 Texas Administrative Code (TAC) §25.53, SMT Ironman BESS, LLC hereby files its updated Emergency Operations Plan ("EOP").

This EOP establishes the procedures, responsibilities, and operational controls necessary to prepare for, respond to, and recover from emergency events affecting personnel, equipment, or operations. This filing is not a joint filing.

Ironman will provide its unredacted Emergency Operations Plan to Commission Staff upon request through encrypted electronic transmission or secure file-sharing platform designated in consultation with Commission Staff in accordance with 16 TAC §25.53(c)(1)(D).

Ironman acknowledges the requirement to submit a full Emergency Operations Plan at least once every three calendar years pursuant to 16 TAC §25.53(c)(3).

Ironman maintains separate Winter and Summer Weatherization Plans that help meet compliance with PUCT Rule 25.55.

1.3 Primary and Backup Emergency Contacts

The below individuals are the primary and backup emergency contacts for Ironman who can immediately address urgent requests and questions from the PUCT during an emergency.

Emergency Coordinators

Primary Emergency Coordinator	Jay Peterson	Jay.peterson@ubs.com	(347)683-3868
Alternate Emergency Coordinator	Kevin Feely	Kevin.feely@ubs.com	(561)703-3847

1.4 TAC §25.53 Requirements Reference

TAC §25.53 Reference	Requirement	Page	EOP Section
(c)(1)(A)(i)(I)	Executive Summary – Policies and Contents	3	Section 1.0
(c)(1)(A)(i)(II)	Executive Summary – Requirements Reference	4	Section 1.4
(c)(4)(A)	Executive Summary – Record of Distribution	5	Section 1.5
(c)(4)(B)	Primary and Backup Emergency Contacts	3	Section 1.3
(c)(4)(C)	Executive Summary - Affidavit	6	Section 1.6
(d)(1)	Approval and Implementation Section	8	Section 3.0
(d)(2)	Communication Plan	10	Section 4.0
(d)(3)	Emergency Response Supplies	12	Section 5.0
(d)(4)	Emergency Staffing	12	Section 6.0
(d)(5)	Weather Hazard Identification and EOP Activation	14	Section 9.0
(e)(2)(A)(i)	Weather Emergency Annex - Operational Plan for Hot/Cold Emergency	19	Weather Emergency Annex
(e)(2)(A)(ii)	Weather Emergency Annex - Fuel Switching Equipment Verification	-	N/A
(e)(2)(A)(iii)	Weather Emergency Annex - Checklist for Supplies and Personnel	20	Weather Emergency Annex
(e)(2)(B)	Water Shortage Annex	-	N/A
(e)(2)(C)	Restoration of Service Annex	22	Restoration of Service Annex
(e)(2)(D)	Pandemic and Epidemic Annex	22	Pandemic and Epidemic Annex
(e)(2)(E)	Hurricane Annex	22	Hurricane Annex
(e)(2)(F)	Cybersecurity Annex	27	Cybersecurity Annex
(e)(2)(G)	Physical Security Annex	28	Physical Security Annex
(e)(2)(H)	Additional Annexes	28	Flooding Annex
(f)	Drill Administration	13	6.0

SMT IRONMAN BESS, LLC | Emergency Operations Plan

1.5 Record of Distribution

Below is a record of all Ironman Personnel with access to the Emergency Operations Plan.

Name	Company	Role	Date of Access
America Alatorre	Radian Generation	Compliance Manager	February, 2025
Jay Peterson	SMT Ironman BESS, LLC	Authorized Signatory	February, 2025
Kevin Feely	SMT Ironman BESS, LLC	Authorized Signatory	February, 2025
Dan Barnard	Canadian Solar	O&M Manager	February, 2025
Jonathan Garcia	Canadian Solar	Field Technician	February, 2025
Paul Morris	Canadian Solar	Maintenance Supervisor	February, 2025
Daniel Lynch	Canadian Solar	Regional Manager	February, 2025
Levi Parker	Canadian Solar	O&M Supervisor	February, 2025

SMT Ironman BESS LLC


Emergency Operations Plan - 2026 Annual Update Affidavit

The undersigned below is the entity's highest-ranking representative, official, or officer with binding authority over SMT Ironman BESS LLC, and affirms the following:

1. Relevant operating personnel are familiar with and have received training on the applicable contents and execution of the EOP, and as such personnel are instructed to follow the applicable portions of the EOP except to the extent deviations are appropriate as a result of specific circumstances during the course of an emergency;
2. The EOP has been reviewed and approved by the appropriate executives;
3. Drills will be conducted to the extent required by subsection (f) of PUCT Rule 25.53;
4. The EOP or an appropriate summary has been distributed to local jurisdictions as needed;
5. SMT Ironman BESS LLC maintains a business continuity plan that addresses returning to normal operations after disruptions caused by an incident; and
6. SMT Ironman BESS LLC's emergency management personnel who are designated to interact with local, state, and federal emergency management officials during emergency events will receive the latest IS-100, IS-200, IS-700, and IS-800 National Incident Management System training by 12/31/2026.


SMT Ironman BESS LLC

By: Energy Storage Investment Fund I, LP,
its direct or indirect member
By: UBS Asset Management (Americas) LLC,
its Investment Advisor and Attorney in Fact


Name: Alex Leung
Title: Authorized Signatory

Name: Martin Lanternier
Title: Authorized Signatory

SWORN TO AND SUBSCRIBED TO BEFORE ME
on the 13th day of March 2026.


Notary Public in and for the State of
New York County of New York

RYAN JAKE LAST NOTARY PUBLIC, STATE OF NEW YORK Registration No. 02LA6337349 Qualified in New York County Commission Expires February 22, <u>2028</u>

2.0 ROLES AND RESPONSIBILITIES

This Plan applies to Ironman described in Section 1.1 of the Plan. This section describes the responsibilities and activities required of various parties in preparation for an emergency. Ironman understands that corporate and facility management, with critical execution and support from Canadian Solar O&M (U.S.) LLC (Canadian Solar), will play an important role in maintaining an effective Plan at the Facility. It is the responsibility of all personnel to exercise good judgment in the performance of this plan.

2.1 Ironman Personnel

- 2.1.1 Role – Operations & Maintenance (O&M) and Owner personnel, which include all roles listed in this section.
- 2.1.2 Responsibilities
 - a. Participate in plan training.
 - b. Follow this plan and perform actions, as described in this Plan.

2.2 Ironman Compliance Team

- 2.2.1 Role – The compliance personnel for the Facility owner
- 2.2.2 Responsibilities:
 - a. Owner of this Plan.
 - b. Administers compliance program for the Facility.
 - c. Responsible for maintaining and implementing, in coordination with O&M and Asset Management Personnel, this Plan.

2.3 Ironman O&M Compliance Manager

- 2.3.1 Role – The compliance manager for the O&M provider of the Facility.
- 2.3.2 Responsibilities:
 - a. Participate in the development and review of this Plan.
 - b. Administers compliance program for the O&M provider

2.4 Operations Control Center (OCC) Manager

- 2.4.1 Role – The manager for the remote OCC of the O&M provider.
- 2.4.2 Responsibilities:
 - a. Responsible for emergency response and essential operations to restore OCC functionality.
 - b. Participate in training.

2.5 Facility Lead

- 2.5.1 Role – The onsite O&M manager.
- 2.5.2 Responsibilities:
 - a. Participate in the administration, execution, and update of the plan.
 - b. Oversee the day-to-day operation of the Facility.
 - c. Serves as the summer and winter readiness coordinator.

- d. Ensures the requirements and processes laid out in this plan are followed by all site Personnel.
- e. Provide feedback to management on this plan and any lessons learned to improve the plan.

2.6 Field Technicians

2.6.1 Role – Administers O&M responsibilities at Facility as part of the O&M provider

2.6.2 Responsibilities:

- a. Coordinate with the Facility Lead to ensure that this Plan is properly executed.
- b. Participate in responses to emergency events at the Facility.
- c. Conduct any Plan readiness reviews and provide reports to management.
- d. Ensure the requirements and processes laid out in this plan are followed by all site Personnel.
- e. Provide feedback to Facility Lead on this Plan and any lessons learned to improve the plan.

2.7 Asset Management

2.7.1 Role – Asset Management personnel for the facility

2.7.2 Responsibilities:

- a. Participate in the administration, execution, and update of the plan.
- b. Coordinates with O&M and other subcontractors in compliance and operations matters.
- c. Participate in training.

2.8 Asset Owner

2.8.1 Role – Investor with primary ownership of the Facility

2.8.2 Responsibilities:

- a. Sign affidavits regarding completion of the plan.
- b. Coordinate with Asset Manager and Ironman Compliance Team on operations and compliance matters.
- c. Participate in training.

3.0 APPROVAL, IMPLEMENTATION, AND REVISION CONTROL

3.1 Ironman Approval and Implementation

Pursuant to 16 TAC § 25.53(d)(1)(B), the following employees are responsible for maintaining and implementing the EOP, as well as those who may change the EOP.

Name	Role	Authority
America Alatorre	Compliance Manager	Approve EOP
Jay Peterson	Authorized Signatory	Edit, Maintain, Implement EOP
Kevin Feely	Authorized Signatory	Edit, Maintain, Implement EOP
Dan Barnard	O&M Manager	Edit, Maintain, Implement EOP

3.2 Seasonal Critical Component Review and Certification

To ensure compliance with seasonal readiness requirements and submission deadlines, SMT Ironman BESS, LLC shall implement the following formal review mechanism for identification and validation of critical components:

Development of Critical Component List

Prior to each seasonal readiness filing (Winter and Summer), the Facility Lead shall develop or update the list of seasonal critical components identified in the applicable Weatherization Plan.

Internal Technical Review

The draft list of seasonal critical components shall be reviewed by:

- O&M Compliance Manager
- Asset Management Representative
- Ironman Compliance Team

The review shall verify:

- Completeness of identified critical equipment
- Alignment with current operating configuration
- Lessons learned from prior season or events
- Consistency with ERCOT and PUCT seasonal guidance.

Timing Requirement

This review must be completed and documented:

- **No later than November 15** for Winter Readiness (submitted by December 1)
- **No later than May 15** for Summer Readiness (submitted by June 1)

Documentation of Review

The Facility Lead shall maintain written evidence of:

- Date of review
- Names and titles of reviewers
- Confirmation that the list is complete and accurate

- Any modifications made during review.

Documentation shall be retained in the Facility compliance repository.

Certification Prior to Submission

The seasonal readiness document shall not be submitted to the Public Utility Commission of Texas until confirmation of completion of the above review process.

This mechanism ensures that the list of seasonal critical components is formally evaluated and validated prior to submission of Winter and Summer readiness documentation.

3.3 Revision Control

Change control for the Plan is managed and owned by the Compliance Team for Ironman. A summary of revisions listed below.

VERSION HISTORY				
VERSION	APPROVED BY	REVISION DATE	DESCRIPTION OF CHANGE	AUTHOR
1.0	Kellie Macpherson	3/25/2025	New procedure	K. Macpherson
2.0	Kellie Macpherson	6/13/2025	Dates updated on NERC Registration	K. Macpherson
3.0	Kellie Macpherson	2/20/2026	Flooding annexure added	K. Macpherson

Version 3.0 of this EOP was approved on 2/20/2026.

Version 3.0 of this Plan supersedes all previous EOPs as of 2/20/2026.

4.0 COMMUNICATION PLAN

4.1 Media

If any Ironman Personnel are contacted by someone claiming to be a media representative, state upfront that no comment can be provided. Request their name, phone number, and their represented publication, and tell them their contact information will be sent to the appropriate party. Do not provide any company or personnel contact information. Personnel contact information contained in this Plan is confidential information.

Notify Asset Management of the request for media communication. Asset Management will coordinate requests for media communication with the Asset Owner.

4.2 Public Utility Commission of Texas (PUCT)

The PUCT has access to the confidential contact information of the Plan, as well as any contact information publicly filed. Requests from the PUCT will depend on the context. If the Primary or Alternate Emergency Coordinator is contacted by PUCT staff related to an emergency event, request their name, title, and phone number, and answer all questions to the best of your ability. Provide any additional contact information including referrals to other emergency response stakeholders.

If a member of the PUCT staff wishes to discuss the content of this EOP or has other regulatory compliance-related questions, direct the PUCT staff to the Asset Manager. Provide the contact information of the Asset Manager if necessary.

4.3 Office of Public Utility Counsel (OPUC)

The OPUC may have access to the confidential contacts of the EOP. If the Primary or Backup Emergency Coordinator is contacted by OPUC staff, refer the caller to the Asset Manager.

4.4 Fuel Suppliers

The Facility is not dependent on fuel suppliers to operate; accordingly, this portion of the Communications Plan required by 16 TAC Sec. 25.53 is inapplicable to Ironman the Facility.

4.5 Local and State Government Entities, Officials, and Emergency Operations Centers

The Facility Lead and the Field Technicians should work directly with local emergency responders including fire, police, or emergency medical services to coordinate services on site.

Any contact from a local government official, such as a city manager, council member, city engineer, or mayor shall refer the communication to Ironman the O&M Compliance Manager, who will coordinate with Ironman the Compliance Team and the Asset Manager for responses.

Requests for coordination with any emergency operations center, such as the Texas Division of Emergency Management (TDEM), shall be referred to Ironman O&M Compliance Manager, who will coordinate with the Ironman Compliance Team and the Asset Manager for responses.

4.6 Reliability Coordinator

The O&M OCC communicates with the Transmission Operator (TOP) and Qualified Scheduling Entity (QSE), as needed and in accordance with ERCOT procedures. The TOP is CenterPoint Energy Houston Electric, LLC and the QSE is Habitat. Real-time operations are coordinated between the 24/7 control centers of these three entities.

The O&M OCC represents the Facility as a Resource Entity in ERCOT, and real-time communications to ERCOT such as outage reporting, telemetry, and verbal dispatch are directed through the QSE.

5.0 PLAN TO MAINTAIN PRE-IDENTIFIED SUPPLIES

Ironman keeps the following pre-identified emergency supply inventory onsite. This inventory checklist is confirmed before each winter and summer season.

Summer Item(s):	Quantity	Notes
Tarps	4	
Battery-powered radio with NOAA weather alert tone	2	
Extension cords	4	
Flashlights and batteries	4	
Portable generator	2	Two 500kW Generators available on demand, will be shared amongst the Ranger 1 Project.
Verify adequate fuel reserves both for backup generator and for ATV/Vehicle fuel		Sufficient fuel capacity in the generators- on call fuel service contract established with local vendor
Hot weather gear that is compatible with PPE (e.g., fire-resistant clothing that breathes, cooling bandanas, sunscreen, personal hydration) ¹	4	Personnel required to travel with PPE. Cases of water to be included in the control room as emergency drinking water supply.
Fully stocked First Aid kits	2	Located in control room
Verify adequate inventory of spare parts for reliable operation of the plant during summer season		Yes Confirmed
Winter Item(s):	Quantity	Notes
Tarps	4	Located in control room
Blankets	4	Located in control room
Battery-powered radio with NOAA weather alert tone	2	Located in control room
Extension cords	4	Located in control room
Flashlights and batteries	6	Located in control room
Fully stocked First Aid kits	2	Located in control room
Verify adequate inventory of spare parts needed for reliable operation during winter weather		Yes confirmed

6.0 EMERGENCY STAFFING PLAN

The O&M team will notify regional staff within a 2-hour dispatch to remain on call for response requirements as needed. This will include technicians assigned to the generator as well as other resources in the vicinity. Should conditions at the facility require manpower beyond the capabilities of the local staff, qualified third-party resources will be engaged as well as O&M personnel beyond the local employees.

7.0 TRAINING

All O&M personnel at the Facility shall receive training on this Emergency Operations Plan whenever it is modified or on at least an annual basis. Contractors and visitors who enter operating areas of the facility will be trained on plant alarms, muster locations, and evacuation procedures before they enter the facility for the first time.

7.1 Annual Drill

The Ironman Compliance Team will ensure that a drill of this plan occurs annually, unless a response to an actual event has occurred in the calendar year that activated this Plan. Upon completion of the drill, the Compliance Team will provide evidence of completion. The Compliance Team will notify PUCT staff at least 30 days before the drill with the date, time, and location of the drill.

7.2 Drill Requirements

The content of each drill will be based on current needs and will be determined by the Compliance Team. The Facility is located in a TDEM-designated hurricane evacuation zone and, the annual drill must include a documented evacuation of the substation control building. If the Facility is located in a hurricane evacuation zone, as defined by the Texas Division of Emergency Management, at least one drill will include a test of the Hurricane Annex.]

A roster of drill attendees and the date of drill was conducted will be filed with this plan and retained in the Facility document repository. Any gaps or action items that are a result of the drill will be identified, resolved, fully documented, and filed with the Facility documents.

8.0 LOCAL EMERGENCY CONTACTS

Ironman Emergency Coordinator is responsible for specific actions detailed in this Plan (as noted). Alternate personnel may serve as the Facility Emergency Coordinator when necessary.

EMERGENCY CONTACTS

9-1-1

Texas Division of Emergency Management – Region 2: 817-372-3068

Hazardous Material Spills (State): 800-832-8224

Weather Warning Center: <https://www.weather.gov/>

Poison Control: (800) 222-1222

Non-Emergency Contacts	Phone:
County Sheriff (use 911 for emergencies)	(979)849-5711
Local Police Department	(979)798-2277
Local Fire Department	903-784-4870
TX Commission on Environmental Quality	512-239-1000
National Response Center (NRC)	800-424-8802
Texas Water Development Board	512-463-7847
OSHA	1-800-321-6742
Texas Parks & Wildlife Department	512-389-4800

9.0 WEATHER HAZARD IDENTIFICATION AND EOP ACTIVATION PROCEDURE

Ironman will identify weather related hazards such as tornadoes, hurricanes, extreme cold weather, extreme hot weather, drought, and flooding through the National Weather Service alert system. The O&M OCC is a 24x7 staffed desk responsible for monitoring NWS alerts. The Compliance Team and Asset Manager also monitors ERCOT notices, including extreme weather notices. The O&M OCC will activate the EOP by notifying the appropriate Ironman Personnel, including the Asset Manager and Ironman Compliance Team, for the specified type of emergency. The procedures of this EOP, including the annexes, will be identified in the emergency communication.

10.0 PERSONNEL INJURIES OR SERIOUS HEALTH CONDITIONS

The following sections provide basic guidelines for response actions to be taken in the event of emergencies related to personnel health. Although facility personnel should take the most aggressive response actions that are prudent in an emergency, the first and foremost action will be to call 911 to initiate the response of trained outside medical responders. To prepare facility personnel for such contingencies, it will be the facility policy that all operating personnel and as many other personnel as possible should be trained in CPR (Cardiopulmonary Resuscitation) and in the use of an AED (Automated External Defibrillator) if one is available. If present on site, the AED will be maintained at the facility at the designated location in the O&M building.

Note: Severe weather condition-related injuries are covered in the appropriate Plan.

Basic First Response Actions

- Check for unresponsiveness. Unresponsiveness is when the person is unconscious and does not respond when you call their name or touch them.
- If the person is unresponsive, immediately call 911 for outside medical assistance and ask other personnel to bring the AED to the scene. Other personnel should assist with 911 notifications and expediting the delivery of the AED to the scene.
- Next check to see if the victim is breathing normally. If no signs of breathing are observed, the responder should initiate two rescue breaths into the victim. After the rescue breaths, a pulse should be checked for on neck. If a pulse is present, continue with recovery breathing, but do not initiate chest compressions.
- If no pulse is observed, complete CPR, with assisted breathing and chest compressions should be commenced.
- If CPR is being performed and the AED arrives to the scene, direct an assistant to begin setting up the AED for operation on the victim. CPR should be continued during the time that the AED is being set up.

- If the AED is placed into operation, remain near the victim and follow all AED instructions to ensure safety and proper victim monitoring. Maintain the victim with AED monitoring until trained medical responders arrive at the scene.
- If the victim is responsive but shows signs of shock or has an obvious severe injury, call 911 immediately and take additional actions as described in the sections below.
- If the victim has obvious broken bones or is bleeding profusely or may have neck or spine injuries, do not attempt to move the victim. Make the victim as comfortable as possible and apply pressure to mitigate areas of profuse bleeding until trained medical personnel arrive at the scene.
- Immobilize all injured parts of the victim.
- Prepare victim for transportation, if the victim can be safely moved

Physical Shock

Symptoms

- Pallid face.
- Cool and moist skin.
- Shallow and irregular breathing.
- Perspiration appearing on the victim's upper lip and forehead.
- Increased, but faint pulse rate.
- Nausea.
- Detached semi-conscious attitude towards what is occurring around him/her.

Treatment

- Request professional medical aid immediately.
- Remain with and attempt to calm the victim.

Electric Shock

Symptoms

- Pale bluish skin that is clammy and mottled in appearance.
- Unconsciousness. No indications that the victim is breathing.

Treatment

- Turn off electricity if possible.
- Call for professional medical assistance and an ambulance immediately.
- Remove electric contact from victim with non-conducting material.
- Perform CPR and call for an AED, if required.

Burns

Symptoms

- Deep red color; or
- Blisters; or
- Exposed flesh.

Treatment

- Cooled immediately if possible, and
- Free of any jewelry or metal if it is safe to remove it.
- Do not pull away clothing from burned skin tissue.
- Do not apply any ointment to burn area.
- Seek professional medical assistance as soon as possible.

11.0 FIRE RESPONSE PLAN

The Facility has a Fire Response Plan that describes measures taken at the facility to prevent, minimize the severity of, and proactively prepare for the event of a fire emergency. However, if a fire should occur at the facility, this Fire Response Plan describes the actions that should be taken by plant personnel. Safe and expedient response actions are essential to protect the health and safety of plant personnel and minimize damage to plant equipment and the surrounding environment.

O&M Field Operations and Safety Personnel schedule an on-site coordination meeting with local Fire and First Responders to establish expectations, cross train on safety concerns and establish expectations in preparation for a fire. They are to discuss access points, personnel points of contact and contact information including O&M OCC. Electrical safety, equipment voltages, currents and arc flash information, safe working distances, electrical isolation with zones of protection as appropriate are to be covered with first responders to ensure safety and develop clear expectation prior to an event.

1. Any person who discovers a fire in the facility should immediately make radio/phone contact with the Facility Lead Technician, and provide the following information:
 - a. That a fire has been discovered.
 - b. The location and source of the fire.
 - c. Any injuries that have occurred
 - d. The cause of the fire (if known)
 - e. Actions they will be taking to extinguish the fire (if appropriate, in accordance with step 2 of this procedure).

NOTE: Notifying others of the emergency and getting trained responders on the way is the most important step in minimizing injuries to personnel and damage to equipment. However, if the person discovering a fire would be significantly delayed in attempting to extinguish it in its incipient stage by first getting to a radio to report it, the priority would be to extinguish the fire in the incipient stage. Example: A fire commences in the immediate vicinity of a person who does not have immediate access to a plant radio. If the person can quickly extinguish the fire, he/she should do so first, then get to a radio to report the fire as soon as possible thereafter. If a fire progresses to or is discovered in a state beyond the incipient stage, the immediate action is to notify others over the radio and get help.

2. Any person discovering a fire in its incipient stage should act as quickly as possible to extinguish the fire. In general, a fire should be considered to be in its incipient stage if it meets two primary criteria:
 - a. The fire can be extinguished or controlled with a single portable fire extinguisher; and

- b. The person discovering the fire perceives an adequate level of safety in attempting to extinguish the fire.
3. As long as the fire is in its incipient stage, as defined above, the person discovering the fire should utilize all appropriate and readily available fire extinguishing equipment to extinguish the fire. Fire-fighting efforts beyond the incipient stage will be performed by trained outside responders only. (Note: All plant personnel will be provided with initial and periodic refresher training on the types and locations of fire-fighting equipment at the facility.
4. In response to the fire, the Facility Lead Technician/Lead Technician will need to make the following determinations:
 - a. The equipment or activities that need to be shut down and/or ceased.
 - b. If any automatic fire suppression systems (if applicable) were activated as a result of the fire, when to secure such systems.

12.0 CHEMICAL OR OIL SPILLS AND RELEASES

The spill or release of any chemical is a potentially serious event, and appropriate response actions must be taken to minimize health hazards to personnel, as well as potential impacts to the environment. It is the policy of the facility that plant personnel will not respond to spills/releases but will instead call for trained outside responders to perform this function. For the purpose of clarification to plant personnel, the term "respond" in this context refers to actions taken to perform cleanup operations of spilled substances, and in some cases may even take the meaning of actually stopping the source of a spill. Taking basic response actions to a spill such as setting up barricades, placing containment media and stopping spills in situations such as the step 1 example below should not be construed to be acting in the role of a "responder", as it is defined in OSHA HAZWOPER regulations.

The basic actions to be taken in response to a chemical spill or release are the following:

1. If the spill or release is the direct result of an operational action performed on the system from which the release has originated, the person who performed the action should attempt to stop the release (if possible) **if it can be stopped without incurring additional personal exposure to the substance**. An example of this might be the following:

Example: A person opens the drain valve on a line that results in an unexpected release. If the person can immediately stop the release by closing the valve, this action should be taken if no additional exposure to the chemical will occur by doing so.
2. The person discovering a spill/release should immediately move to a location that is a safe distance from the affected area, but still allows for observation of the affected area (if remaining within observation distance is safe under prevailing conditions; if in doubt, do not risk exposure – leave the area.).
3. The person discovering the spill should look for other personnel in the area and warn them by any means available of the event that has occurred. The Facility Lead Technician/Lead technician should be notified immediately over the radio. Information provided should include all of the following that are known:
 - a. What type of chemical has been spilled/released?
 - b. The location(s) of the spill/release.
 - c. If the source of the spill/release has been stopped
 - d. If any injuries or chemical exposure has occurred to personnel.

- e. Boundaries describing the area of the spill.
 - f. Whether or not the spill is contained.
 - g. Quantity released.
 - h. Environmental Impacts (water bodies, streams, ground, roadways).
4. Based upon the report from the person discovering the spill, the Facility Lead Technician/Lead Technician shall evaluate whether the circumstances pose a threat to the surrounding community or the environment. **If a threat is imposed to the community or environment, 911 should be notified immediately.**
5. The Facility Lead Technician/Lead Technician shall make a determination as to whether the spill/release is of a quantity that must be reported to agencies, and if so, which agencies to notify. To perform this step, the Facility Lead Technician/Lead Technician shall use the Spill Prevention Control and Countermeasure Plan (SPCC). The Facility Lead Technician shall ensure that all required notifications are made.
6. While remaining at a safe distance from the spill/release, the person discovering the spill should locate and place temporary containment around the outer boundaries of the spill, and place absorbent mats over any plant drains that are near the location of the spill. **This should be performed only if it is safe to do so without risking chemical exposure.**
7. The person discovering the spill should attempt to barricade, restrict access or otherwise mark off safe boundaries around the spill to avert others from inadvertently approaching the spill area. **This should be performed only if it is safe to do so without risking chemical exposure.**
8. The person discovering the spill should remain at a safe distance from the source of the spill/release until additional assistance or instructions are received.
9. Unless the person discovering the spill has reported unsafe conditions for approach of the area, the Facility Lead Technician shall immediately proceed to the spill area to evaluate the severity of the incident. **NOTE: IF ANY PERSONNEL ARE DISCOVERED TO BE UNCONSCIOUS OR OTHERWISE INCAPACITATED UPON APPROACH TO THE SPILL SCENE, ALL PERSONNEL MUST IMMEDIATELY BACK AWAY TO A SAFE DISTANCE FROM THE UNKNOWN THREAT.**
10. The Facility Lead Technician/Lead Technician shall evaluate the adequacy of containment, barricades, and any other efforts that have been taken to prevent the spill from migrating to any additional areas or systems, and direct additional actions to be performed (unless it is deemed that any additional actions are unsafe to perform). The adequacy or need for PPE should also be assessed. Upon completing this assessment, the Facility Lead Technician/Lead Technician shall notify/inform the Facility Emergency Coordinator of the status of the emergency.
11. Once the Facility Lead Technician/Lead Technician has determined that adequate containment and barricading of the spill area exists, he/she shall ensure that an adequately trained observer remains positioned a safe distance from the scene to observe the status of the spill. This observer shall perform radio status checks a minimum of once every three minutes until outside responders arrive for cleanup/mitigation actions.

ANNEXES

WEATHER EMERGENCY ANNEX

Severe weather can negatively impact the Facility. Events and disturbances that can occur in and around the Facility include, but are not limited to, windstorms, severe thunderstorms, flooding, tornadoes, hurricanes, excessive heat or cold, snowstorms, and ice storms. These weather events can be detrimental to the employees and or equipment and structures at the facility.

Prior to any severe weather event, Personnel should utilize the plans and checklists contained in the weatherization plans to ensure the safety of both personnel and equipment. The information contained herein is supplemental and should be used in conjunction with those plans.

Temperature Design Parameters

The Facility has a design maximum ambient and Operating temperature of 104 degrees Fahrenheit and Facility has design minimum ambient and Operating temperature of -13 degrees Fahrenheit.

Event Identification

Ironman team monitors weather through multiple outlets, including National Weather Service alerts, local weather alerts, and regional entity notification distributions. When a weather emergency is identified by Ironman team, the appropriate procedure is put into effect, which includes pre-event and during event checklists to ensure safety and reliability.

Operational Plan for Cold Weather Emergency

Ironman Winter Weatherization Plan includes Appendices for both seasonal readiness in accordance with §25.53, and pre-event checklists in accordance with §25.55. Ironman Personnel will use the Pre-Event Appendix when the Weather Emergency – Cold Weather Emergency is activated. Also included are Appendices related to emergency supplies and post-season lessons learned.

The Pre-event Checklist to be used upon activation of the EOP is incorporated into the Winter Weatherization Plan is repeated below for compliance purposes:

PRE-WINTER CHECKLIST

Date Completed:			
Completed By:			
Item	Description	Complete? Y/N	Notes
1	Establish staff responsibilities regarding weather monitoring and alerting		
2	Develop a list of Cold Weather Critical Components that require increased attention during winter weather events		
3	Consider the need for application of freeze protection on critical equipment		
4	Confirm backup power supply/generator is functional, if applicable		
5	Complete Equipment Inventory and replenish any items that are deficient		
6	Review emergency response contacts (fire, EMS, etc.) and ensure they are clearly posted onsite		

Operational Plan for Hot Weather Emergency

Ironman Summer Weatherization Plan includes Appendices for both seasonal readiness in accordance with §25.53, and pre-event checklists in accordance with §25.55. Ironman Personnel will use the Pre-Event Appendix when the Weather Emergency – Hot Weather Emergency is activated. Also included are Appendices related to emergency supplies and post-season lessons learned.

The Pre-event Checklist to be used upon activation of the EOP is incorporated into the Summer Weatherization Plan is repeated below for compliance purposes:

PRE-SUMMER CHECKLIST/HOT WEATHER PREPAREDNESS CHECKLIST

Date preparedness activities performed		
Completed by Plant Manager or Designee		
Item	Description	Complete? Y/N
1.	Review summer outage reporting requirements with management.	
2.	Ensure all weed abatement work orders are scheduled and completed prior to the onset of the summer season.	
3.	Establish and document staff responsibilities to monitor weather and receive weather alerts.	
4.	Establish and document a communications plan with the O&M Control Center.	
5.	Develop a list of critical equipment that require increased surveillance during extreme heat or severe summer weather events.	
6.	Monitor and address any bird nesting in or around the high voltage substation	
7.	Inspect building penetrations, windows, doors, fan louvers, and other openings for potential exposure of critical equipment to the elements. Ensure O&M and Substation control building cooling systems can maintain cooling loads.	
8.	Check equipment inventory and replenish all quantities. Refer to Appendix 1 for inventory. Confirm completeness and expiration dates of First Aid kit contents. Confirm PPE in use by all personnel.	
9.	Ensure availability of sufficient drinking water for all personnel on site (up to 2 gallons per person per day). Ironman well water is not suitable for drinking without additional filtration.	
10.	Review and update emergency response personnel contacts for emergency response (specifically fire and EMS).	
11.	Check vehicles maintenance schedule	

Personnel Safety

If shelter-in-place is necessary, on-site personnel should seek indoor shelter in the O&M building or substation control room. Personnel should remain indoors if the severe weather is affecting the immediate area of the facility and maintain communications with the O&M OCC.

Verification of the Adequacy and Operability of Fuel Switching Equipment

This component of the Weather Emergency Annex is not relevant to Ironman because it does not have fuel switching equipment installed.

WATER SHORTAGE ANNEX

Sufficient water is kept onsite for staff consumption and housekeeping. The Facility does not require process water to operate.

RESTORATION OF SERVICE ANNEX

In the event of a loss of external site power, there is an automatic transfer switch that initiates backup battery power to maintain power to the site control systems. This allows the site to maintain visibility of the site until the O&M representative can perform a site assessment. The target response time for this scenario is two (2) hours after weather or safety conditions permit.

Restoration of service is coordinated between the OCC and ERCOT (via the QSE) using proper protocols to ensure safety and reliability. If remote capability is lost for any reason, the site can be re-energized locally after it is deemed safe to do so.

PANDEMIC AND EPIDEMIC ANNEX

Procedures related to management of a pandemic or epidemic primarily affect Ironman Personnel present on site. Procedures to prevent the spread of illness amongst staff physically located on site are tailored to the known transmission mechanisms of the disease. The Generator Operator Compliance Manager is responsible for developing and training the personnel on site for disease-specific transmission protection procedures.

HURRICANE ANNEX

Hurricanes, tropical storms, and other severe weather is monitored by Ironman personnel through multiple outlets. Once identified, a storm's progress is tracked to consider the severity and path of the storm. In the event a hurricane or tropical storm impact is imminent, operational preparations may be taken based on manufacturer design, including wind stow function of modules, reinforcing structures, or site de-energization.

Evacuation

If the Facility Lead Technician determines that a facility evacuation is necessary, he/she must determine which type of evacuation to direct. The following sections describe the types of evacuations that can be performed:

Immediate Site Evacuation

This type of evacuation would be used only in the event of an emergency grave enough to warrant immediate evacuation of all personnel. In this type of evacuation, operating area personnel should evacuate without regard for shutdown of plant systems or for placing plant

systems in the safest mode possible. This type of evacuation should only be utilized if the safety of personnel in operating areas is in immediate and severe danger, such that any delay in evacuating could result in deaths or injuries to personnel.

Delayed Site Evacuation

This type of evacuation would be used in a serious emergency where non-essential personnel (those not involved in plant operations or emergency coordination) are immediately evacuated as a precaution, and essential personnel remain in operating areas to perform a controlled shutdown of the facility prior to evacuating. It is anticipated that this would be the primary type of evacuation used in response to serious emergencies at the facility. The Facility Lead Technician and/or Facility Emergency Coordinator must assess whether the prevailing circumstances warrant keeping essential personnel in plant operating areas to perform a controlled shutdown of the facility. If personnel will not be exposed to unnecessary danger to perform facility shutdown and/or place the facility into a safe condition, then this is the preferred type of evacuation, as opposed to an Immediate Site Evacuation.

*NOTE: Although the Facility Lead Technician (or Facility Emergency Coordinator) may initially designate an evacuation to be a Delayed Site Evacuation, he/she should always keep in mind that conditions may change rapidly, and result in the need to call for an Immediate Site Evacuation.

The Facility Lead Technician or lead technician onsite will determine if an evacuation is necessary.

Evacuation will be coordinated via the company cell phone. Teams will be alerted if an evacuation has been directed. If an evacuation has been directed, the Facility Lead Technician shall ensure that instructions for evacuation are communicated to personnel over the plant radio system or hand-held radios. These instructions should include the following items at a minimum:

- The type of evacuation to be performed
- Immediate Site Evacuation
- Delayed Site Evacuation
- The nature of the emergency
- The location(s) of the emergency
- Any egress routes that should not be used by evacuating personnel (if known and applicable)

If an evacuation has been ordered, personnel shall follow either the Immediate Site Evacuation Procedures or Delayed Site Evacuation Procedures contained in Appendix 4, as appropriate, and based upon the direction of the Facility Lead Technician and/or Facility Emergency Coordinator.

Immediate Site Evacuation Procedure

1. Personnel present on-site at the O&M Building shall immediately take the following actions:
 - a. Locate and obtain the visitor/contractor sign-in sheet.
 - b. Locate and obtain all immediately accessible hand-held radios.
 - c. Gather at the front entrance gate at facility, and determine the safest muster area to proceed to, depending upon the known circumstances of the emergency (as indicated on Appendix 3).

*NOTE: The primary muster area must be a predetermined location, with any alternate muster areas selected only when egress routes to the primary muster area are unsafe to proceed along.

- d. Pass the following information over the plant radio system:
 - i. The muster area the employees will be proceeding to.
 - ii. Visitors/contractors known to be in the operating areas (as indicated by the visitor/contractor sign-in sheet).
 - e. Once emergency personnel have completed the preceding steps, they shall immediately proceed to their designated muster area. Personnel on-site should not delay in evacuating or wait on other personnel that they anticipate may arrive.
 - f. Upon arriving at the designated muster area, the group shall designate a Person-in-Charge and take a head count of all personnel who are at the muster area, including contractors and visitors.
 - g. After a roll call of all personnel present at the muster area is taken, the Person-in-Charge shall identify which operating area personnel are not accounted for. The Person-in-Charge will then query by radio for personnel who are unaccounted for. The Person-in-Charge shall then establish radio communication with the Emergency Coordinator (if applicable) and relay information on personnel who are not accounted for.
 - h. All personnel at the muster location shall remain at the muster location until an "ALL CLEAR" signal is sounded, or if directed by the Emergency Coordinator (if applicable) to leave the muster location. The "ALL CLEAR" signal will be communicated by radio or cellular telephone.
 - i. The Person-in-Charge shall continuously monitor the plant radio system when at the muster location.
2. Personnel present in the field/substation area (other than the O&M Building) shall immediately perform the following actions:
- a. If not monitoring the plant radio system, immediately turn on hand-held radios.
 - b. Proceed to the designated muster area unless the egress route to the muster area is not safe for travel. In such a case, proceed to an alternate muster area.
 - c. Instruct any personnel (including visitors and contractors) who are seen along the way to proceed to the designated muster area.
 - d. Upon reaching the appropriate muster area, report to the Person-in-Charge and continue to monitor the plant radio system. If no other personnel are present at the muster area upon arrival, communicate to the Facility Lead Technician that no other personnel are present in the area.
3. Personnel not in the operating areas of the plant (to include the O&M building and parking areas) shall immediately perform the following actions:
- a. Locate and obtain all immediately accessible hand-held radios.
 - b. Proceed to the designated muster area.

- c. A Person-in-Charge shall be designated for the muster area. In many cases, this will be the Emergency Coordinator. The Person-in-Charge shall establish radio communications with operating area personnel and compare roll call lists to determine if any personnel are unaccounted for in the facility.
- d. If the Emergency Coordinator is not present at the muster area, the Person-in-Charge at the muster area will coordinate outside responding agency activities until the Emergency Coordinator arrives. In the event that the Emergency Coordinator is in plant operating areas or has proceeded to the alternate muster area, he/she may elect to designate the muster area Person-in-Charge to act in the capacity of Emergency Coordinator during the emergency

Delayed Site Evacuation Procedures

1. Personnel present on-site at the O&M building shall immediately take the following actions:
 - a. Take necessary operating actions to place the facility in the most stable condition, based upon the type of emergency.
 - b. Locate and obtain the visitor/contractor sign-in sheet
 - c. Communicate names of visitors/contractors currently in the operating areas to outside operating personnel. Instruct outside operating personnel to locate and direct all visitors/contractors to proceed to the Administrative Building for egress instructions.
 - d. When all visitors, contractors and non-essential operating personnel have been accounted for and are present in the O&M building, the Facility Lead Technician or Emergency Coordinator, as appropriate shall designate a trained person to escort all non-essential personnel to the designated muster area along the safest egress route.
 - e. Notify the Emergency Coordinator of the current facility status, and evacuation details.
 - f. Perform a controlled shutdown in accordance with appropriate procedures and directions from the Emergency Coordinator.
 - g. Once the shutdown has been completed, all essential personnel shall gather in the O&M and take roll call. When all essential operating personnel are present and accounted for, evacuation to the designated muster area shall be performed, unless the egress route is not safe for travel. In such a case, proceed to the alternate muster area.
2. Personnel present in the field/substation area (other than the O&M building) shall immediately perform the following actions:
 - a. Continuously monitor the radio system for information and instructions.
 - b. Perform immediate response actions, as appropriate, to place the facility in the most stable condition, based upon the type of emergency.
 - c. Locate and direct non-essential personnel to proceed to the O&M building immediately.
 - d. Perform facility shutdown instructions as directed by the Facility Lead

Technician/Lead technician.

- e. Upon completion of shutdown, or upon direction by the Emergency Coordinator, proceed to the muster point for instructions.
3. Personnel not in the operating areas of the facility (to include the O&M building and parking areas) shall immediately perform the following actions:
 - a. Locate and obtain all immediately accessible hand-held radios. (b) Proceed to the designated muster area (see Site Map).
 - b. A Person-in-Charge shall be designated for the muster area. The Person-in- Charge shall establish radio communications with operating area personnel and compare roll call lists to determine if any personnel are unaccounted for in the facility.
 - c. The Person-in-Charge at the designated muster area will coordinate outside responding agency activities and provide assistance (to include personnel, resources, and administrative functions) to the O&M building as directed by the Emergency Coordinator and/or Facility Lead Technician/Lead technician.
4. The Emergency Coordinator shall immediately perform the following actions:
 - a. Proceed to the O&M building or to the location on the facility most appropriate for directing response actions for the emergency.
 - b. Coordinate actions related to the emergency and provide directions to muster area.
5. Persons-in-Charge
 - a. In the event that the emergency escalates in severity or immediate danger to personnel, direct immediate evacuation of all essential operating personnel involved in plant shutdown activities.

Designated Egress Routes and Muster Areas for Evacuations

- The Designated Muster Area is the primary gathering point for personnel and should be used during evacuations unless the emergency has rendered egress routes to the Muster Area unsafe for travel.
- The Alternate Muster Area is the alternate gathering point for such circumstances.
- Alternate muster location will be communicated at the time of evacuation and will take into consideration the event occurring that is causing the evacuation

Primary Muster Area	Facility entry point
Alternate Muster Area	Outside BESS yard fence boundary closest to road



Re-Entry Procedures

Facility personnel will review site re-entry procedures with the Facility Lead. Facility personnel should tour the site grounds to observe possible hazards including:

- Compromised O&M Building integrity
- Compromised Substation Control room integrity
- Panels pulled from tracker racking from wind forces
- Foreign debris washed against the fence line
- Water driven Erosion of site roads, substation grade, and inverter pads

CYBERSECURITY ANNEX

Cybersecurity for the Facility is managed by a third-party Managed Security Services Provider. The administered network security program includes firewall monitoring, VPN controls, and network security. Approval for remote access to Facility equipment and use of transient cyber assets and removeable media are monitored and approved by the third-party Managed Security Services Provider. Ironman Regular training is conducted for relevant Ironman Personnel.

PHYSICAL SECURITY ANNEX

Objectives for Physical Security Controls

Ironman has selected a set of operational, procedural and/or technical security controls to control physical access, based on its need, for both the electronic and physical security perimeter.

a. Facility Physical Security Controls

Ironman employs the following site perimeter controls.

- a. A clearly identifiable physical perimeter surrounds the Facility or Facilities.
- b. The perimeter fencing has posted "Danger - High Voltage, Keep Out" signage.
- c. Gates in the perimeter fencing are kept locked.

Ironman employs the following procedural controls.

- a. Personnel are expected to, at a minimum:
 - Notify the O&M OCC prior to entering the substation control building and receive permission to enter;
 - Only enter areas they have authorization to enter;
 - Close and lock gates, doors, and cabinets behind them, as appropriate; and
 - Report suspicious activity.

All electronic access controls for Ironman's low impact BES Cyber Systems are contained within the substation control building or in cabinets with bolted- doors within the Facility perimeter.

Ironman employs the following physical access controls.

- d. The following physical access controls are employed at the substation control building:
 - Door contacts that are alarmed via SCADA;
 - Lock to the substation yard;
 - Lock to the substation house.
- e. The following access controls are employed at the O&M building:
 - Lock to the O&M building.

FLOODING ANNEX

This Flooding Annex establishes the procedures, responsibilities, and operational controls that Ironman will implement to prepare for, respond to, and recover from flooding events that may impact Facility personnel, equipment, or operations.

This Annex is developed in accordance with 16 TAC §25.53(e) and addresses identification, preparedness, response, and restoration activities related to flood hazards.

Flood Risk Identification

Ironman evaluates flood risk using the following sources:

- National Weather Service (NWS) flood watches and warnings
- ERCOT weather notices and emergency communications
- FEMA Flood Insurance Rate Maps (FIRM), where applicable
- Local county emergency management notifications
- Historical site drainage and stormwater assessments

The Facility Lead and O&M OCC monitor flood-related alerts on a 24/7 basis.

Flood risk factors evaluated include:

- Proximity to rivers, creeks, or drainage channels
- Stormwater retention pond capacity
- Site grading and drainage pathways
- Elevation of inverter pads, transformers, and substation equipment
- Access road vulnerability

If a flood watch or warning is issued for the county or immediate vicinity of the Facility, the EOP may be activated at the discretion of the Facility Lead or O&M OCC.

Pre-Flood Preparedness Actions

Upon identification of credible flood risk, the following actions shall be taken as applicable:

1. Verify operability of SCADA and remote monitoring systems.
2. Confirm backup battery systems and auxiliary power sources are functional.
3. Inspect drainage ditches, culverts, and stormwater pathways for blockage.
4. Secure loose materials and mobile equipment.
5. Confirm containment measures for oil-filled equipment are intact.
6. Verify emergency contact list and communication protocols.
7. Evaluate the need for site de-energization if water intrusion risk to critical equipment is identified.

All preparedness activities shall be documented.

Operational Response During Flood Event

If flooding impacts or threatens the Facility:

- Personnel safety is the first priority.
- Personnel shall not enter flooded electrical areas.
- Standing water near energized equipment shall be treated as energized until verified otherwise.
- The Facility Lead will determine if site evacuation is required in accordance with the Hurricane Annex evacuation procedures.

- The O&M OCC shall coordinate with the QSE and ERCOT regarding operational status.
- If required for safety or equipment protection, a controlled shutdown will be initiated.

Access to the Facility shall be restricted if roadways become unsafe.

Post-Flood Assessment and Re-Entry

Re-entry shall occur only when floodwaters have receded and conditions are deemed safe.

The following inspections shall be conducted prior to re-energization:

1. Visual inspection of substation equipment and inverter stations.
2. Inspection for water intrusion in control enclosures and buildings.
3. Verification of grounding system integrity.
4. Inspection of erosion affecting equipment pads and structural stability.
5. Infrared or insulation resistance testing of affected equipment, as required.
6. Verification that oil containment systems remain intact and uncompromised.

No equipment shall be re-energized until cleared by qualified personnel.

Communication and Reporting

The Facility Lead shall:

- Notify the Compliance Team and Asset Management of flood impacts.
- Make required regulatory notifications if environmental release occurs.
- Coordinate restoration with the O&M OCC, TOP, and QSE.
- Document all actions taken under this Annex.

If environmental releases occur due to flooding, reporting shall follow the Chemical or Oil Spill procedures.

Training and Drills

Flood response procedures shall be included in annual EOP training.

Where applicable, flood scenarios may be incorporated into annual drills in accordance with 16 TAC §25.53(f).


SMT Ironman BESS LLC

Emergency Operations Plan - 2026 Annual Update Attestation

The undersigned below is the entity's highest-ranking representative, official, or officer with binding authority over SMT Ironman BESS LLC and attests that SMT Ironman BESS LLC has made revisions to its Emergency Operations Plan to incorporate a Flooding Annex consistent with the updates to PUCT Substantive Rule 25.53. These revisions ensure compliance with the rule requirements. No other material modifications affecting the entity's emergency response procedures have been made.


SMT Ironman BESS LLC

By: Energy Storage Investment Fund I, LP,
its direct or indirect member
By: UBS Asset Management (Americas) LLC,
its Investment Advisor and Attorney in Fact


Name: Alex Leung
Title: Authorized Signatory

Name: Martin Lanternier
Title: Authorized Signatory

SWORN TO AND SUBSCRIBED TO BEFORE ME
on the 13th, day of March 2026.


Notary Public in and for the State of
New York, County of New York.

RYAN JAKE LAST NOTARY PUBLIC, STATE OF NEW YORK Registration No. 02LA6337349 Qualified in New York County Commission Expires February 22, _____

SMT Ironman BESS LLC

Emergency Operations Plan - 2026 Annual Update Emergency Contact Pleading

The undersigned below is the entity's highest-ranking representative, official, or officer with binding authority over SMT Ironman BESS LLC and affirm that there have been no changes to the primary or backup emergency contacts for SMT Ironman BESS LLC.

SMT Ironman BESS LLC

By: Energy Storage Investment Fund I, LP,
its direct or indirect member
By: UBS Asset Management (Americas) LLC,
its Investment Advisor and Attorney in Fact

ILS. G
Name: Alex Leung
Title: Authorized Signatory

Name: Martin Lanternier
Title: Authorized Signatory

SWORN TO AND SUBSCRIBED TO BEFORE ME
on the 13th, day of March 2026.

Ryan Jake Last
Notary Public in and for the State of
New York, County of New York.

RYAN JAKE LAST NOTARY PUBLIC, STATE OF NEW YORK Registration No. 02LA6337349 Qualified in New York County Commission Expires February 22, <u>2028</u>
